






SITE PLAN/GRADING PLAN
 C.C.W.D. HEADQUARTERS
 MAINTENANCE AND WAREHOUSE BUILDING
 CALAVERAS COUNTY, CALIFORNIA
 ADJUSTED LOT 10 (NOVEMBER 2019)
 NORDAHL LAND SURVEYING

SITE ADDRESS
 120 TOMA COURT
 SAN ANDREAS, CA 95249
OWNER
 MICHAEL MINKLER, GENERAL MANAGER
 CALAVERAS COUNTY WATER DISTRICT
 120 TOMA COURT
 SAN ANDREAS, CA 95249
ENGINEER
 KEVIN WILLIAMS, P.E.
 CALAVERAS COUNTY WATER DISTRICT

WEST BEN INC
 INST#2004-24050
 LOT 9 F.M. 11-94

DETAILS



- CONSTRUCTION NOTES: GENERAL**
- PERMITS ARE REQUIRED BY THE COUNTY OF CALAVERAS AND OTHER PERMITTING AGENCIES; NO CONSTRUCTION SHALL BE INITIATED WITHOUT PLANS APPROVED BY ALL PERMITTING AUTHORITIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE OWNER TO OBTAIN THE REQUIRED PERMITS, IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COMPLY WITH PERMITS.
 - THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL REQUIREMENTS INCLUDING THOSE CONTAINED IN THE CALAVERAS COUNTY CODE.
 - CONTRACTOR SHALL CONTACT THE PERMITTING AUTHORITY(IES) AT LEAST 48 HOURS PRIOR TO START OF CONSTRUCTION TO ARRANGE FOR ON-SITE PRE-CONSTRUCTION MEETING(S)
 - TO ALLOW FOR INSPECTION, ALL WORK SHALL BE PERFORMED DURING DAYLIGHT HOURS, MONDAY-FRIDAY. NO WORK SHALL BE PERFORMED DURING HOLIDAYS.
 - CONTRACTOR SHALL CONTACT UNDERGROUND SERVICE ALERT FOR UTILITY LOCATION PRIOR TO EXCAVATION.
 - ALL MATERIALS AND WORK PERFORMED SHALL BE IN ACCORDANCE WITH PLANS, PROJECT SPECIFICATIONS AND CALAVERAS COUNTY DEPARTMENT OF PUBLIC WORKS CQA PLAN.
- CONSTRUCTION NOTES: GRADING**
- ANY REQUIRED CONSTRUCTION STAKING TO BE IN PLACE PRIOR TO BEGINNING CONSTRUCTION.
 - CONTRACTOR SHALL IMPLEMENT "BEST MANAGEMENT PRACTICES (BMP'S)" TO CONTROL EROSION AND REDUCE THE OFF-SITE DISCHARGE OF SEDIMENT TO THE MAXIMUM EXTENT POSSIBLE, INCLUDING PERMITTER CONTROLS (FIBER ROLL/SILT FENCE), STABILIZED CONSTRUCTION ENTRANCE (ROCK ENTRANCE/EXIT), CHECK DAMS IN GUTTER FLOW LINES (GRAVEL BAGS) AND DRAINAGE INLET PROTECTION (GRAVEL BAGS/FILTER BAGS).
 - DUST GENERATING MUST BE MINIMIZED AND A WATER TRUCK MUST BE AVAILABLE ON-SITE WHEN NECESSARY FOR ADEQUATE DUST CONTROL.
 - CONTRACTOR SHALL KEEP ADJOINING STREETS AND DRIVEWAYS FREE OF DIRT, MUD AND OTHER PROJECT RELATED DEBRIS THROUGHOUT CONSTRUCTION. ANY DAMAGE TO PUBLIC STREETS OR ROADWAYS SHALL BE REPAIRED AT SOLE COST AND EXPENSE OF CONTRACTOR.
 - FILL MATERIALS SHALL BE COMPACTED TO RELATIVE COMPACTION OF NOT LESS THAN 90% AND NOT LESS THAN 95% UNDERNEATH BUILDING PAD AND PAVED AREAS.
 - THE GROUND SURFACE SHALL BE PREPARED TO RECEIVE FILL BY REMOVING VEGETATION, NON-COMPLYING FILLS, TOPSOIL AND OTHER UN-SUITABLE MATERIALS. ALL STUMPS AND DEBRIS SHALL BE HAULED AWAY.
 - CUT AND FILL SLOPES SHALL BE NO STEEPER THAN 2:1 (HORIZONTAL TO VERTICAL).
 - NO MORE THAN ONE ACRE SHALL BE DISTURBED. IF MORE THAN ACRE IS DISTURBED, THE CONTRACTOR MUST PREPARE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND APPLY FOR PERMIT WITH CENTRAL VALLEY REGIONAL WALTER QUALITY CONTROL BOARD.
 - ALL GRADING SHALL COMPLY WITH PROJECT SPECIFICATION, PROJECT DRAWINGS, CALIFORNIA BUILDING CODE AND PERMIT REQUIREMENTS OF CALAVERAS COUNTY DEPARTMENT OF PUBLIC WORKS.
- CONSTRUCTION NOTES: STORM DRAIN**
- STORM DRAIN CULVERT SHALL BE 24" CORRUGATED METAL PIPE (12 GAGE). ALL JOINTS SHALL BE WATERTIGHT.
 - MINIMUM SLOPE OF STORM DRAIN SHALL BE 1%. STORM DRAIN SHALL HAVE 30" COVER UNDER PAVED SURFACE.
 - TRENCH WIDTH SHALL BE AT LEAST 24" WIDER THAN THE DIAMETER OF THE PIPE TO BE INSTALLED. THE TOTAL TRENCH SHALL BE BACKFILLED WITH STRUCTURAL BACKFILL.



DESIGNED BY: K. WILLIAMS
 DRAFTED BY: K. WILLIAMS
 CHECKED BY:
 DATE: 7/26/2021
 SCALE: NO SCALE
 BAR LENGTH ONE INCH ON SCALED DRAWING

REVISION:	DESCRIPTION:	DATE:	BY:



CALAVERAS COUNTY WATER DISTRICT
 120 TOMA COURT
 SAN ANDREAS, CALIFORNIA 95249
 PHONE: (209) 754-3543

SITE PLAN
 C.C.W.D HEADQUARTERS
 MAINTENANCE AND WAREHOUSE BUILDING PROJECT


11101
PROJECT NUMBER
C1
DRAWING NUMBER
SHEET NUMBER

GENERAL NOTES

- DESIGN BASED ON 1500 PSF ALLOWABLE SOIL BEARING PRESSURE.
- CONSTRUCTION SHALL CONFORM TO THE 2019 CALIFORNIA BUILDING CODE AND ALL REQUIREMENTS OF THE COUNTY OF CALAVERAS BUILDING DEPARTMENT.
- SPECIAL INSPECTION IS REQUIRED IN ACCORDANCE WITH 2019 CBC FOR HIGH STRENGTH A325 BOLTS. SPECIAL INSPECTOR MUST BE EMPLOYED BY THE OWNER AND APPROVED BY THE COUNTY OF CALAVERAS BUILDING DEPARTMENT. INSPECTOR'S REPORTS NOTING DISCREPANCIES, IF ANY, TO BE FILED WITH THE BUILDING DIVISION WEEKLY DURING CONSTRUCTION, WHETHER CORRECTED OR NOT. ALL INSPECTORS' DAILY LOGS TO BE MAINTAINED ON SITE FOR REVIEW BY THE COUNTY INSPECTORS, AND C.C.W.D.
- THE FOUNDATION/FOOTING DESIGN WAS CALCULATED USING ASD LOAD COMBINATIONS AND THE COLUMN REACTIONS PROVIDED BY CECO BUILDING SYSTEMS ON SHEETS F1 - F3 FOR JOB # 18-B-20989.
- THE ANCHOR BOLT EMBEDMENT WAS CALCULATED USING LRFD LOAD COMBINATIONS AND THE COLUMN REACTIONS PROVIDED BY CECO BUILDING SYSTEMS ON SHEETS F1 - F3 FOR JOB # 18-B-20989.
- THE FOOTING BASE PLATE, ANCHOR BOLT SIZES AND LOCATIONS ARE PROVIDED BY CECO BUILDING SYSTEMS ON SHEETS F1 - F3 FOR JOB # 18-B-20989.
- FOOTING SIZE MAY BE INCREASED UP TO 12" PER SIDE AT CONTRACTOR'S OPTION.

CONCRETE NOTES

- CONCRETE SHALL HAVE MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 4,000 PSI (6 SACK)
- CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 2,500 psi, WITH SLUMP NOT TO EXCEED 4". AGGREGATE SHALL BE A MAXIMUM OF 1-3/4" IN FOUNDATIONS AND 3/4" IN THE SLAB. CURING COMPOUND SHALL BE APPLIED TO THE SLAB IMMEDIATELY AFTER FINAL TROWELLING.
- FOR CRACK CONTROL PROVIDE 3/4" DEEP TOOL JOINT/SAW CUT AT 10'-0" MAX SPACING, BOTH DIRECTIONS.
- REINFORCING BAR TO BE GRADE 40 (MIN) WITH 30" LAP SPLICES. MAINTAIN 3" CLEARANCE WHEN POURED AGAINST SOIL AND 2" ELSEWHERE. WELDED WIRE MESH (WWM) SHALL BE LAPPED NOT LESS THAN TWO WIRE SPACES. BARS ARE TO BE CONTINUOUS AROUND CORNERS.
- IF EXPANSIVE SOILS ARE PRESENT - SATURATE THE SOIL TO A DEPTH OF 24" PRIOR TO POURING CONCRETE.
- USE 6-MIL MOISTURE BARRIER WITH JOINTS LAPPED NOT LESS THAN 6 INCHES BETWEEN BASE OR SUBGRADE AND THE CONCRETE FLOOR SLAB, (ASTM E 1745) WHERE FLOORING OR MOISTURE SENSITIVE EQUIPMENT WILL OVERLAY CONCRETE SLABS.



CONCRETE SLAB NOTES

- 6" PCC SLAB ON 4" AGGREGATE BASE
- CONTINUOUS 12" X 12" PERIMETER FOOTING
- MIN. REINFORCEMENT: FIBERMESH OR APPROVED EQUAL

8-LBS. FIBERMESH/CY

FOUNDATION PLAN - SCHEMATIC ONLY
NOT TO SCALE

ANCHOR BOLT SCHEDULE


1A-C, 1B-A, 1C-A, 1D-B, 4B-F, 4C-F, 9A-B, 9B-A, 9C-A & 9D-B	2A-D, 2D-D, 3A-D, 3D-D, 4A-D, 4D-D, 5A-D, 5D-D, 6A-D, 6D-D, 7A-D, 7D-D, 8A-D & 8D-D
(2) 5/8 INCH PAB5 (X10) EMBEDDED 18 INCHES PROJECTING 2 INCHES	(4) 3/4 INCH PAB6 (X14) EMBEDDED 18 INCHES PROJECTING 2.5 INCHES

NOTES:


- FOR BASE PLATE SIZE, LOCATIONS AND ANCHOR BOLT SPACING SEE SHEETS F1 - F3 PROVIDED BY CECO BUILDING FOR JOB# 18-B-20989.
- ALL NON-STRUCTURAL ANCHOR BOLTS FOR OPENINGS AND DOORS SHALL HAVE A MINIMUM ANCHOR BOLT EMBEDMENT OF 4", SHALL HAVE 2" PROJECTING, ARE MARKED WITH \otimes AND ARE SHOWN ON THIS SHEET FOR REFERENCE ONLY. SEE SHEETS F1 - F3 PROVIDED BY CECO BUILDING FOR JOB# 18-B-20989 FOR PLACEMENT.
- PAB5 = 5/8 INCH \emptyset PRE ASSEMBLED BOLT.
PAB6 = 3/4 INCH \emptyset PRE ASSEMBLED BOLT.
- ANCHOR BOLTS ARE TO BE EITHER GRADE 36, A36, A307 OR ASTM F1554. THE WASHER SHALL BE 1/2" THICK & 1-3/4" SQUARE FOR 5/8" ANCHOR BOLT AND 2-1/4" SQUARE FOR 3/4" ANCHOR BOLT MINIMUM. IF THERE IS A 'H' AFTER PAB# THOSE BOLTS NEED TO BE OF A HIGH STRENGTH STEEL SUCH AS ASTM A449.

FOOTING SCHEDULE


1A 2'-9" SQ x 1'-6" TH 3-#4 EACH WAY @ 9.00' O.C. TOP & BOTTOM	2A, 2D, 3A, 3D, 4A, 4D, 5A & 5D 4'-0" SQ x 2'-6" TH 8-#4 EACH WAY @ 5.25' O.C. TOP & BOTTOM
1B, 1C, 9B & 9C 2'-9" SQ x 1'-6" TH 3-#4 EACH WAY @ 7.625' O.C. TOP & BOTTOM	6A, 6D, 7A, 7D, 8A & 8D 3'-8" SQ x 2'-6" TH 7-#4 EACH WAY @ 5.375' O.C. TOP & BOTTOM
1D, 9A & 9D 1'-5" SQ x 1'-6" TH 2-#4 EACH WAY @ 5.50' O.C. TOP & BOTTOM	4B & 4C 1'-0" SQ x 1'-0" TH 1-#4 EACH WAY @ 6.00' O.C. TOP & BOTTOM




HAIRPIN AT SIDEWALL
NOT TO SCALE




HAIRPIN AT CORNER
NOT TO SCALE



SPREAD FOOTING, TYP.
NOT TO SCALE



CONTINUOUS FOOTING AT ROLL UP DOOR
NOT TO SCALE



CONTINUOUS FOOTING
NOT TO SCALE



140 YELLOWSTONE DRIVE,
SUITE 110
CHICO, CALIFORNIA 95973
TEL (530) 809-1315
FAX (530) 517-6020

WES@WGILBERTENGINEERING.COM
CIVIL ENGINEERING
SURVEYING
PROPERTY SURVEYS
CONSTRUCTION STAKING



Designed by: *Wesley E. Gilbert* 6/15/2021

MR. KEVIN WILLIAMS, P.E.
**METAL BUILDING
FOUNDATION & FOOTING PLAN
120 TOMA COURT**
STATE OF CALIFORNIA
COUNTY OF CALAVERAS

REV.	DATE	DESCRIPTION

F1
DATE: JUNE 15, 2021
DRAWN BY: WJN
DESIGNED BY: WJN
CHECKED BY: WEG
JOB NO.: 18-B-20989

W:\Projects\18-B-20989\18-B-20989 (Williams)\V - Footing Plan 18-B-20989 (Williams)\06021.dwg FOUNDATION
 06/15/2021 10:07 am WJN

BUILDER/CONTRACTOR RESPONSIBILITIES

Drawing Validity – These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

Builder Acceptance of Drawings – Approval of the manufacturer’s drawings and design data affirms that the manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer’s interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC code of standard practice APR 10 Section 4.4.1)

Code Official Approval – It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

Builder is responsible for State, Federal and OSHA safety compliance – The Builder/Contractor is responsible for applying and observing all pertinent safety rules and regulations and OSHA standards as applicable.

Building Erection – The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector. (AISC Code of Standard Practice APR 10 Section 7.10.3)

Discrepancies – Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC Code of Standard Practice APR 10 Section 3.3)

Materials by Others – All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturers assumptions will govern.

Modification of the Metal Building from Plans – The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a Licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

Foundation Design – The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA MBSM Chapter 4 Section 3.2.2 and Section A3)

PROJECT NOTES

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, or ASTM A1011 with 55 ksi min. yield, except flanges wider than 12” and thicker than 3/8”, all flanges thicker than 1”, and all webs thicker than 3/8” are 50 ksi min. yield. Rod X-bracing conforms to ASTM A529 or ASTM A572 with 50 ksi min. yield. Cable X-bracing conforms to ASTM A475 7 Strand Extra High-Strength grade. Hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with 50 ksi min. yield. Hot rolled angles, other than flange braces, conform to ASTM A36 minimum. Round and rectangular HSS conforms to ASTM A500 Grade B. Cold-formed steel secondary framing Members conform to ASTM A1011 or ASTM A653 Grade 55 with 55 ksi min. yield.

The manufacturer does not assume any responsibility for the erection nor field supervision of the structure and or any special inspections that may be required by the local building authority during erection (including inspection of the high strength bolts or field welds) as required during erection. The coordination and the costs associated for setting up and Special Inspections are the responsibility of the Erector, Owner, Architect, or Engineer of Record.

Design is based upon the more severe loading of either the roof snow load or the roof live load.

Loads, as noted, are given within order documents and are applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the manufacturer nor the certifying engineer declares or attests that the loads as designated are proper for the local provisions that may apply or for site specific parameters. The manufacturer’s Engineer’s certification is limited to design loads supplied by an Architect and/or engineer of record for the overall construction project.

This project is designed using manufacture’s standard serviceability standards. Generally this means that all stresses and deflections are within typical performance limits for normal occupancy and standard metal building products. If special requirements for deflections and vibrations must be adhered to, then they must be clearly stated in the contract documents.

”The design collateral load has been uniformly applied to the design of the building. Hanging loads are to be attached to the purlin web. This may not be appropriate for heavily concentrated loads. Any attached load in excess of 150 pounds shall be accounted for by special design performed by a licensed engineer using concentrated loads and may require separate support members within the roof system.”

Using 5x5 southern eave gutter with 4 x 5 downspouts, the roof drainage system has been designed using the method outlined in the MBMA Metal Building Systems Manual. Downspout locations have not been located on these drawings. The downspouts are to be placed on the building sidewalls at a spacing not to exceed 50 feet with the first downspout from both ends of the gutter run within 25 feet of the end. Downspout spacing that does not exceed the maximum spacing will be in compliance with the building code. The gutter and downspout system as provided by the manufacturer is designed to accommodate 2.5 in/hr rainfall intensity.

ENGINEERING DESIGN CRITERIA

Building Code..... CBC 19
 Building Risk Category..... II – Normal

Roof Dead Load
 Superimposed..... 1.750 psf
 Collateral..... 3 psf (Total)
 (0.00 psf Ceiling 3 psf Other)
 Roof Live Load.....20.00 psf reducible

Snow
 Ground Snow Load (Pg)..... 0.00 psf
 Snow Load Importance Factor (Is) 1.00
 Snow Exposure Factor (Ce)..... 1.00
 Thermal Factor (Ct)..... 1.00
 Flat Roof Snow Load (Pf)..... 0 psf

Wind
 Ultimate Wind Speed (Vult)..... 95 mph
 Nominal Wind Speed (Vasd)..... 74 mph
 (IBC Section 1609.3.1)
 Serviceability Wind Speed..... 65 mph
 Wind Exposure Category..... C
 Internal Pressure Coefficient (GCpi) 0.55 / –0.55
 Loads for components not provided by building manufacturer:
 Wall Edge Zones 23.62 psf pressure
 –29.48 psf suction
 Other Wall Zones 23.62 psf pressure
 –25.08 psf suction

These values are the maximum values required based on a 10 square foot area.
 Components with larger areas may have lower wind loads.
 Zones per ASCE 7–16; FIG. 30.3–1
 Zones pressures shown are Un–Factored

Seismic
 Seismic Importance Factor (Ie)..... 1.00
 Seismic Design Category..... D
 Soil Site Class..... d
 Ss..... 0.430 g Sds..... 0.417 g
 S1..... 0.222 g Sd1..... 0.319 g
 Analysis Procedure..... Equivalent Lateral Force

Location...	Int	RF	Front	SW	Back	SW	Left	EW	Right	EW
System.....	C4	B3	B3	B3	B3	B3				
R.....	3.25	3.25	3.25	3.25	3.25	3.25				
Cs.....	0.128	0.128	0.128	0.128	0.128	0.128				

Design Base Shear in kips (V) Transverse 10.04
 Design Base Shear in kips (V) Longitudinal 10.04

Basic Structural System (from ASCE 7–16 Table 12.2–1)
 System – Basic Force Resisting System
 H – Steel System not Specifically Detailed for Seismic Resistance
 C4 – Steel Ordinary Moment Frames
 B3 – Steel Ordinary Concentric Braced Frames
 G2 – Steel Ordinary Cantilevered Column Systems
 R – Response Modification Coefficient
 Cs – Seismic Response Coefficient
 Transverse – Direction Parallel to the Rigid Frames
 Longitudinal – Direction Perpendicular to the Rigid Frames

Drawing Index	
Page	Description
C1	COVER SHEET
F1	ANCHOR BOLT PLAN
F2	ANCHOR BOLT REACTIONS
F3	ANCHOR BOLT DETAILS
E1	ROOF FRAMING PLAN
E2	ROOF SHEETING PLAN
E3	FRONT SIDEWALL
E4	BACK SIDEWALL
E5	LEFT ENDWALL
E6	RIGHT ENDWALL
E7–E8	FRAME CROSS SECTION
E9	PARTITION FRAMING & SHEETING
DET1–10	STANDARD DETAILS
R1–R3	INSTALLATION SHEETS

DRAWING STATUS

FOR APPROVAL
 These drawings, being For Approval, are by definition not final, and are for conceptual representation only. Their purpose is to confirm proper interpretation of the project documents. Only drawings issued "For Erector Installation" can be considered as complete.

FOR CONSTRUCTION PERMIT
 These drawings, being for Permit, are by definition not final. Only drawings issued "For Erector Installation" can be considered as complete.

FOR ERECTOR INSTALLATION
 Final drawings for construction.

For questions or assistance
 Concerning Erection call:
252–977–2131
 Monday–Friday 7:30am to 5:00pm

ENGINEERING SEAL

The engineer whose seal appears hereon is an employee for the manufacturer for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.



Download panel installation manuals from:
www.ncimanuals.com

Descargue los manuales de instalación del panel desde:
www.ncimanuals.com

1/2"Ø A325 BOLT GRIP TABLE		
GRIP	LENGTH	BOLT LENGTH
0 TO 9/16"	1 1/4" F.T.	<p>NOTE: FULL THREAD ENGAGEMENT IS DEEMED TO HAVE BEEN MET WHEN THE END OF THE BOLT IS FLUSH WITH THE FACE OF THE NUT.</p> <p>WASHER REQUIRED ONLY WHEN SPECIFIED. WASHER MAY BE LOCATED UNDER HEAD OF BOLT, UNDER NUT, OR AT BOTH AT LOCATIONS NOTED ON ERECTION DRAWINGS. ADD 5/32" FOR EACH WASHER TO MATERIAL THICKNESS TO DETERMINE GRIP.</p>
Over 9/16" TO 1 1/16"	1 3/4" F.T.	
Over 1 1/16" TO 1 5/16"	2"	
Over 1 5/16" TO 1 9/16"	2 1/4"	
Over 1 9/16" TO 1 13/16"	2 1/2"	
Over 1 13/16" TO 2 1/16"	2 3/4"	
LOCATIONS OF BOLTS LONGER THAN 2 3/4" NOTED ON ERECTION DRAWINGS		
F.T. DENOTES FULLY THREADED		


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328–6722
 Mount Pleasant, IA. (319) 385–8001
 Rocky Mount, NC. (252) 977–2131
www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT		OWNER: CALAVERAS COUNTY WATER DISTRICT	
CUSTOMER: THE STEEL BUILDER		LOCATION: SAN ANDREAS, CA 95249	
CAD	DATE	SCALE	PHASE
A	5/11/21	N.T.S.	1
BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
A	18–B–20989	C1	0

May 19, 2021
Stephanie Lynn Schwindt
 Drawing has been digitally signed



ANCHOR BOLT PLAN

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER: CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	F1	0

May 19, 2021
Stephanie Lynn Schwindt
Drawing has been digitally signed.

GENERAL NOTES

- THE REACTIONS PROVIDED ARE BASED ON THE ORDER DOCUMENTS AT THE TIME OF MAILING. ANY CHANGES TO BUILDING LOADS OR DIMENSIONS MAY CHANGE THE REACTIONS. THE REACTIONS WILL BE SUPERSEDED AND VOIDED BY ANY FUTURE MAILING.
- REACTIONS ARE PROVIDED AS UN-FACTORED FOR EACH LOAD GROUP APPLIED TO THE COLUMN. THE FOUNDATION ENGINEER WILL APPLY THE APPROPRIATE LOAD FACTORS AND COMBINE THE REACTIONS IN ACCORDANCE WITH THE BUILDING CODE AND DESIGN SPECIFICATIONS TO DETERMINE BEARING PRESSURES AND CONCRETE DESIGN. THE FACTORS APPLIED TO LOAD GROUPS FOR THE STEEL COLUMN DESIGN MAY BE DIFFERENT THAN THE FACTORS USED IN THE FOUNDATION DESIGN.
- THE MANUFACTURER DOES NOT PROVIDE "MAXIMUM" LOAD COMBINATION REACTIONS. HOWEVER, THE INDIVIDUAL LOAD REACTIONS PROVIDED MAY BE USED BY THE FOUNDATION ENGINEER TO DETERMINE THE APPLICABLE LOAD COMBINATIONS FOR HIS/HER DESIGN PROCEDURES AND ALLOW FOR AN ECONOMICAL FOUNDATION DESIGN.
- THE METAL BUILDING MANUFACTURER IS RESPONSIBLE FOR THE DESIGN OF THE ANCHOR BOLT DIAMETER ONLY TO PERMIT THE TRANSFER OF FORCES BETWEEN THE BASE PLATE AND THE ANCHOR BOLT IN SHEAR, BEARING AND TENSION, BUT IS NOT RESPONSIBLE FOR THE ANCHOR BOLT EMBEDMENT FOR TRANSFER OF FORCES TO THE FOUNDATION. THE METAL BUILDING MANUFACTURER DOES NOT DESIGN AND IS NOT RESPONSIBLE FOR THE DESIGN, MATERIAL AND CONSTRUCTION OF THE FOUNDATION EMBEDMENTS. THE END USE CUSTOMER SHOULD ASSURE HIMSELF THAT ADEQUATE PROVISIONS ARE MADE IN THE FOUNDATION DESIGN FOR LOADS IMPOSED BY COLUMN REACTIONS OF THE BUILDING, OTHER IMPOSED LOADS, AND BEARING CAPACITY OF THE SOIL AND OTHER CONDITIONS OF THE BUILDING SITE. IT IS RECOMMENDED THAT THE ANCHORAGE AND FOUNDATION OF THE BUILDING BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER EXPERIENCED IN THE DESIGN OF SUCH STRUCTURES, (SECTION A3 MBMA 2006 METAL BUILDING SYSTEMS MANUAL).
- BOTTOM OF ALL BASE PLATES ARE AT THE SAME ELEVATION. (UNLESS NOTED)
- ANCHOR RODS ARE ASTM F1554 GRADE 36 MATERIAL UNLESS NOTED OTHERWISE.

ENDWALL COLUMN:

BASIC COLUMN REACTIONS (k)

Frm Line	Col Line	Dead Vert	Collot Vert	Live Vert	Wind_Left1 Horz	Wind_Left1 Vert	Wind_Right1 Horz	Wind_Right1 Vert	Wind_Left2 Horz	Wind_Left2 Vert	Wind_Right2 Horz	Wind_Right2 Vert	Wind_Press Horz	Wind_Press Vert
1	D	0.4	0.3	2.1	0.0	-2.4	0.0	-2.1	0.0	-0.4	0.0	-0.1	0.0	0.0
1	C	0.6	0.7	4.4	-1.8	-7.1	0.0	-2.1	-1.8	-3.6	0.0	1.4	-3.6	0.0
1	B	0.6	0.7	4.4	0.0	-2.0	1.6	-6.9	0.0	1.6	1.7	-3.4	-3.6	0.0
9	A	0.4	0.3	2.1	0.0	-2.5	0.0	-2.8	0.0	-0.6	0.0	-0.9	0.0	-2.8
9	A	0.4	0.3	2.1	0.0	-2.4	0.0	-2.1	0.0	-0.4	0.0	-0.1	0.0	0.0
9	B	0.6	0.7	4.4	-1.8	-7.1	0.0	-2.1	-1.8	-3.6	0.0	1.4	-3.6	0.0
9	C	0.6	0.7	4.4	0.0	-2.0	1.6	-6.9	0.0	1.6	1.7	-3.4	-3.6	0.0
9	D	0.4	0.3	2.1	0.0	-2.5	0.0	-2.8	0.0	-0.6	0.0	-0.9	-1.5	0.0

Frm Line	Col Line	Wind_Suct Horz	Wind_Suct Vert	Wind_Long1 Horz	Wind_Long1 Vert	Wind_Long2 Horz	Wind_Long2 Vert	Seis_Left Horz	Seis_Left Vert	Seis_Right Horz	Seis_Right Vert	Seis_Long Horz	Seis_Long Vert
1	D	0.0	0.0	0.0	-2.2	0.0	-1.5	0.0	0.0	0.0	0.0	0.0	0.0
1	C	3.8	0.0	0.0	-5.1	-0.4	-4.2	-1.1	-1.0	0.0	1.0	0.0	0.0
1	B	3.8	0.0	0.4	-4.2	0.0	-5.1	0.0	1.0	1.1	-1.0	0.0	0.0
1	A	0.0	2.8	0.0	-1.5	0.0	-2.2	0.0	0.0	0.0	0.0	0.0	-4.6
9	A	0.0	0.0	0.0	-2.2	0.0	-1.5	0.0	0.0	0.0	0.0	0.0	0.0
9	B	3.8	0.0	0.0	-5.1	-0.4	-4.2	-1.1	-1.0	0.0	1.0	0.0	0.0
9	C	3.8	0.0	0.4	-4.2	0.0	-5.1	0.0	1.0	1.1	-1.0	0.0	0.0
9	D	1.7	0.0	0.0	-1.5	0.0	-2.2	0.0	0.0	0.0	0.0	0.0	0.0

NOTES FOR REACTIONS

BUILDING REACTIONS ARE BASED ON THE FOLLOWING BUILDING DATA:

- WIDTH (FT) = 60
- LENGTH (FT) = 160
- EAVE HEIGHT (FT) = 16 / 16
- ROOF SLOPE (rise/12) = 2.0:12 / 2.0:12
- DEAD LOAD (psf) = 1.750
- COLLATERAL LOAD (psf) = 3
- ROOF LIVE LOAD (psf) = 20.00 (REDUCIBLE)
- FRAME LIVE LOAD (psf) = 12
- ROOF SNOW LOAD (psf) = 0
- GROUND SNOW LOAD (psf) = 0.00
- WIND SPEED (MPH) = 95
- NOMINAL WIND SPEED (Vasd) = 74 mph (IBC Section 1609.3.1)
- SERVICEABILITY WIND SPEED = 65 mph
- WIND CODE = CBC 19
- EXPOSURE = C
- CLOSED/OPEN = Partial
- IMPORTANCE - WIND = 1.00
- IMPORTANCE - SEISMIC = 1.00
- SEISMIC ZONE = D

REACTION KEY:

- WIND Left/Right 1 = (with +GCpi Internal Pressure)
- WIND Left/Right 2 = (with -GCpi Internal Pressure)
- Wind_Long 1 = Wind Load Case B at Left EW
- Wind_Long 2 = Wind Load Case B at Right EW
- MIN_SNOW = Minimum Snow (Pm) per code
- E#UNB_SL_L = Endwall Unbalanced Snow Left
- E#UNB_SL_R = Endwall Unbalanced Snow Right
- F#UNB_SL_L = Rigid Frame Unbalanced Snow Left
- F#UNB_SL_R = Rigid Frame Unbalanced Snow Right

ANCHOR BOLT SUMMARY


Qty	Locate	Dia (in)	Type	Proj (in)
○ 36	Jamb	5/8"	F1554	2.00
○ 16	Endwall	5/8"	F1554	2.00
⊗ 56	Frame	3/4"	F1554	2.50
○ 4	Partition	5/8"	F1554	2.00

BUILDING BRACING REACTIONS

Wall Loc	Col Line	Reactions in plane of wall ± Reactions(k)	Panel_Shear (lb/ft)	
			Wind	Seis
L_EW	1	C,B Bracing, see EW reactions		
F_SW	A	1,2 4.0 * 5.0 *		
R_EW	9	B,C Bracing, see EW reactions		
B_SW	D	3,2 4.0 * 5.0 *		

*See EW reactions table for vertical reaction.
*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

FRAME LINES: 2 3 4 5 6 7 8



RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc._Bolt Qty	Anc._Bolt Dia	Base_Plate (in) Width	Base_Plate (in) Length	Thick	Grout (in)
2*	D	4	0.750	6.000	10.50	0.375	0.0
2*	A	4	0.750	6.000	10.50	0.375	0.0

2* Frame lines: 2 3 4 5

RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc._Bolt Qty	Anc._Bolt Dia	Base_Plate (in) Width	Base_Plate (in) Length	Thick	Grout (in)
6*	D	4	0.750	6.000	10.50	0.375	0.0
6*	A	4	0.750	6.000	10.50	0.375	0.0

6* Frame lines: 6 7 8

RIGID FRAME: BASIC COLUMN REACTIONS (k)

Frame Line	Column Line	Dead Horiz	Dead Vert	Collateral Horiz	Collateral Vert	Live Horiz	Live Vert	Wind_Left1 Horiz	Wind_Left1 Vert	Wind_Right1 Horiz	Wind_Right1 Vert	Wind_Left2 Horiz	Wind_Left2 Vert
2*	D	0.8	1.8	1.1	1.8	4.1	8.0	-6.7	-13.1	-0.9	-9.5	-5.5	-2.3
2*	A	-0.8	1.8	-1.1	1.8	-4.1	8.0	0.9	-9.5	6.7	-13.1	-0.3	1.3
6*	D	0.8	1.9	1.1	1.8	4.2	8.0	-6.8	-13.1	-0.9	-9.5	-5.5	-2.3
6*	A	-0.8	1.9	-1.1	1.8	-4.2	8.0	0.9	-9.5	6.8	-13.1	-0.3	1.3

Frame Line	Column Line	Wind_Right2 Horiz	Wind_Right2 Vert	Wind_Long1 Horiz	Wind_Long1 Vert	Wind_Long2 Horiz	Wind_Long2 Vert	Seismic_Left Horiz	Seismic_Left Vert	Seismic_Right Horiz	Seismic_Right Vert	Seismic_Long Horiz	Seismic_Long Vert
2*	D	0.3	1.3	-3.0	-14.1	-3.5	-12.8	-0.8	-0.4	0.8	0.4	0.0	-4.6
2*	A	5.5	-2.3	3.5	-12.8	3.0	-14.1	-0.8	0.4	0.8	-0.4	0.0	-4.6
6*	D	0.3	1.3	-3.0	-11.2	-3.5	-9.9	-0.8	-0.4	0.8	0.4	0.0	0.0
6*	A	5.5	-2.3	3.5	-9.9	3.0	-11.2	-0.8	0.4	0.8	-0.4	0.0	0.0

2* Frame lines: 2 3 4 5
6* Frame lines: 6 7 8

ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc._Bolt Qty	Anc._Bolt Dia	Base_Plate (in) Width	Base_Plate (in) Length	Thick	Grout (in)
1	D	2	0.625	7.000	10.00	0.250	0.0
1	C	2	0.625	7.000	10.00	0.250	0.0
1	B	2	0.625	7.000	10.00	0.250	0.0
1	A	2	0.625	7.000	10.00	0.250	0.0
9	A	2	0.625	7.000	10.00	0.250	0.0
9	B	2	0.625	7.000	10.00	0.250	0.0
9	C	2	0.625	7.000	10.00	0.250	0.0
9	D	2	0.625	7.000	10.00	0.250	0.0

PARTITION ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Dead Load	Wind Press Horz	Wind Suct Horz
4	B	0	-0.97	0.97
4	C	0	-0.97	0.97








ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER	OWNER:	CALAVERAS COUNTY WATER DISTRICT				
LOCATION:	SAN ANDREAS,CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	F2	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
STATE OF CALIFORNIA
C 90667
Civil Engineer



AR Dia 5/8" Framed Opening AR Layout



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP





Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT		OWNER: CALAVERAS COUNTY WATER DISTRICT	
CUSTOMER: THE STEEL BUILDER			
LOCATION: SAN ANDREAS, CA 95249			
CAD	DATE	SCALE	PHASE
	5/11/21	N.T.S.	1
BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
A	18-B-20989	F3	0

May 19, 2021
Stephanie Lynn Schwindt
Drawing has been digitally signed.

** = SAME FLANGE




The large leg of the Zee must be alternated from top to bottom in order to nest the member correctly. A triangle has been added to the end of the Zee near the connection holes, that will point to the large leg of the member.

EXTENSION/CANOPY BOLTS				
ROOF PLAN				
MARK	QUAN	TYPE	DIA	LENGTH
EB-2 W/SC561	4	A325	1/2"	1 1/4"
EB-3 W/SC560	4	A325	1/2"	1 3/4"
EB-4 W/SC560	4	A325	1/2"	1 3/4"
EB-5 W/SC561	4	A325	1/2"	1 1/4"
EB-6 W/SC561	4	A325	1/2"	1 1/4"

SPECIAL BOLTS					
ROOF PLAN					
ID	QUAN	TYPE	DIA	LENGTH	WASH
1	4	A325	1/2"	1 1/4"	0
2	2	A325	1/2"	1 1/4"	2

MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
OC08-1	OC0814	7'-2 3/8"
EB-2	8F25C14	3'-8 13/16"
EB-3	W8X10	3'-8 13/16"
EB-4	W8X10	3'-8 13/16"
EB-5	8F25C14	3'-8 13/16"
EB-6	8F25C14	3'-8 13/16"
P-1	8X25Z16	22'-5 1/2"
P-2	8X25Z16	23'-11 1/2"
P-3	8X25Z16	22'-11 1/2"
P-4	8X25Z16	22'-11 1/2"
P-5	8X25Z16	22'-5 1/2"
E-1	8ES2L14	19'-3 1/2"
E-2	8ES2L14	19'-4"
E-3	8ES2L14	19'-4"
E-4	8ES2L14	19'-4"
E-5	8ES2L14	19'-4"
E-6	8ES2L14	19'-3 1/2"
E-7	8ES2L14	19'-3 1/2"
E-8	8ES2L14	19'-4"
E-9	8ES2L14	19'-3 1/2"
E-10	8X35C14	19'-11 1/2"
E-11	8X35C14	19'-11 1/2"
E-12	8X35C14	19'-11 1/2"
E-13	8X35C14	19'-11 1/2"
E-14	8X35C14	19'-11 1/2"
E-15	8X35C14	19'-11 1/2"
CB-4	1/2" DIA. ROD	27'-5"
CB-5	1/2" DIA. ROD	22'-8"

CONNECTION PLATES	
ROOF PLAN	
ID	MARK/PART
1	DB1



ROOF FRAMING PLAN

- GENERAL NOTES:
- INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
 - ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 - STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
 - DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
 - DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
 - AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E1	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt

 Licensed Professional Engineer
 Stephanie Lynn Schwindt
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA

NOTE:
 LTP'S TO BE FIELD LOCATED
 & FIELD CUT BY OTHERS
 INSTALLATION MUST COMPLY WITH
 OSHA REQUIREMENTS



ROOF SHEETING PLAN

PANELS: 26 Gauge PBR - Galvalume
 [A] SOFFIT PANELS: 26 Gauge PBR - Desert Sand

- GENERAL NOTES:
1. INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
 2. ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
 4. DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
 5. DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
 6. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E2	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt
 LICENSED PROFESSIONAL ENGINEER
 Stephanie Lynn Schwindt
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA




SIDEWALL FRAMING: FRAME LINE A


MEMBER TABLE		
FRAME LINE A		
MARK	PART	LENGTH
DJ-1	8X35C14	15'-2 11/16"
DH-1	8X35C14	11'-11 3/4"
E-1	8ES2L14	19'-3 1/2"
E-2	8ES2L14	19'-4"
E-3	8ES2L14	19'-4"
E-4	8ES2L14	19'-4"
E-5	8ES2L14	19'-4"
E-6	8ES2L14	19'-3 1/2"
G-4	8X25Z16	21'-5 1/2"
G-5	8X25Z16	22'-11 1/2"
G-6	8X25Z16	5'-1 3/4"
G-7	8X25Z16	5'-1 3/4"
G-8	8X25Z16	21'-5 1/2"
CB-2	5/8" DIA. ROD	24'-11"
CB-3	5/8" DIA. ROD	25'-2"
JB-1	8X35C14	1'-11 1/8"

CONNECTION PLATES	
FRAME LINE A	
ID	MARK/PART
1	CL753
3	CL751
4	SC425
5	SC585_L
6	SC585_R

FLANGE BRACE TABLE			
COLUMN LINE A			
ID	MARK	PART	LENGTH
1	FB30	L2X2X14G	2'-6"



FO CLIP MARKING ELEVATION



SIDEWALL SHEETING & TRIM: FRAME LINE A

PANELS: 26 Gauge PBR - Desert Sand

DOWNSPOUT SPACING LOCATIONS
 DOWNSPOUTS ARE TO BE PLACED AT A SPACING NOT TO EXCEED 50 FT. WITH A DOWNSPOUT WITHIN 25 FT. OF EACH END OF THE GUTTER RUN. GUTTER STRAPS TO BE 2'-0" ON CENTER.

GENERAL NOTES:
 1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT		OWNER: CALAVERAS COUNTY WATER DISTRICT					
CUSTOMER: THE STEEL BUILDER		LOCATION: SAN ANDREAS, CA 95249					
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E3	0


May 19, 2021
Stephanie Lynn Schwindt
 Drawing has been digitally signed.
STEPHANIE LYNN SCHWINDT
 LICENSED PROFESSIONAL ENGINEER
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA

MEMBER TABLE		
FRAME LINE D		
MARK	PART	LENGTH
DJ-1	8X35C14	15'-2 11/16"
DH-1	8X35C14	11'-11 3/4"
E-2	8ES2L14	19'-4"
E-4	8ES2L14	19'-4"
E-5	8ES2L14	19'-4"
E-7	8ES2L14	19'-3 1/2"
E-8	8ES2L14	19'-4"
E-9	8ES2L14	19'-3 1/2"
G-5	8X25Z16	22'-11 1/2"
G-6	8X25Z16	5'-1 3/4"
G-7	8X25Z16	5'-1 3/4"
G-8	8X25Z16	21'-5 1/2"
G-9	8X25Z16	3'-7 3/4"
CB-3	5/8" DIA. ROD	25'-2"
JB-1	8X35C14	1'-11 1/8"


CONNECTION PLATES	
FRAME LINE D	
ID	MARK/PART
1	CL753
3	CL751
4	SC425
5	SC585_L
6	SC585_R



SIDEWALL FRAMING: FRAME LINE D



FO CLIP MARKING ELEVATION



SIDEWALL SHEETING & TRIM: FRAME LINE D

PANELS: 26 Gauge PBR - Desert Sand

DOWNSPOUT SPACING LOCATIONS

DOWNSPOUTS ARE TO BE PLACED AT A SPACING NOT TO EXCEED 50 FT. WITH A DOWNSPOUT WITHIN 25 FT. OF EACH END OF THE GUTTER RUN. GUTTER STRAPS TO BE 2'-0" ON CENTER.

GENERAL NOTES:

1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT		OWNER: CALAVERAS COUNTY WATER DISTRICT					
CUSTOMER: THE STEEL BUILDER		LOCATION: SAN ANDREAS, CA 95249					
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E4	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
 LICENSED PROFESSIONAL ENGINEER
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA



BEARING FRAME ONLY!
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.


BOLT TABLE FRAME LINE 1				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2	4	A325	5/8"	1 3/4"
EC-1/ER-1	4	A325	1/2"	1 1/4"
Int_Column/Raf	4	A325	1/2"	1 1/4"
EC-4/ER-2	4	A325	5/8"	1 1/2"

MEMBER TABLE FRAME LINE 1		
MARK	PART	LENGTH
EB-2	8F25C14	3'-8 13/16"
EB-5	8F25C14	3'-8 13/16"
EC-1	10F25C14	14'-7 7/8"
EC-2	10F35C12	17'-10 1/2"
EC-3	10F35C12	17'-10 1/2"
EC-4	10F35C14	14'-10 9/16"
ER-1	8F35C12	30'-6 1/16"
ER-2	8F35C12	30'-6 1/16"
G-1	8X25Z14	18'-7 3/4"
G-2	8X35Z14	19'-4"
G-3	8X25Z14	18'-1 1/2"
CB-1	1/2" DIA. ROD	26'-7"

FLANGE BRACE TABLE FRAME LINE 1			
ID	MARK	PART	LENGTH
1	FB29.3	L2X2X14G	2'-5 1/4"
2	FB7-1	L2.5X2.5X3/16"	2'-5 1/4"

CONNECTION PLATES FRAME LINE 1	
ID	MARK/PART
1	SC-5
2	PC22-1

ENDWALL FRAMING: FRAME LINE 1



ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Gauge PBR - Desert Sand


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E5	0

- GENERAL NOTES:**
- INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 - WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 - OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
 - AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.



FB7 Flange Brace Detail

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
 LICENSED PROFESSIONAL ENGINEER
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA



ENDWALL FRAMING: FRAME LINE 9


BEARING FRAME ONLY!
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLT TABLE FRAME LINE 9				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-3	4	A325	5/8"	1 3/4"
Columns/Raf	4	A325	1/2"	1 1/4"

MEMBER TABLE FRAME LINE 9		
MARK	PART	LENGTH
EB-5	8F25C14	3'-8 13/16"
EB-6	8F25C14	3'-8 13/16"
EC-1	10F35C14	14'-7 7/8"
EC-2	10F35C12	17'-10 1/2"
EC-3	10F35C12	17'-10 1/2"
EC-5	10F25C14	14'-7 7/8"
ER-1	8F35C12	30'-6 1/16"
ER-3	8F35C12	30'-6 1/16"
G-1	8X25Z14	18'-7 3/4"
G-2	8X35Z14	19'-4"
CB-1	1/2" DIA. ROD	26'-7"

FLANGE BRACE TABLE FRAME LINE 9			
ID	MARK	PART	LENGTH
1	FB29.3	L2X2X14G	2'-5 1/4"
2	FB7-1	L2.5X2.5X3/16"	2'-5 1/4"

CONNECTION PLATES FRAME LINE 9	
ID	MARK/PART
1	SC-5



ENDWALL SHEETING & TRIM: FRAME LINE 9

PANELS: 26 Gauge PBR - Desert Sand

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT		OWNER: CALAVERAS COUNTY WATER DISTRICT					
CUSTOMER: THE STEEL BUILDER		LOCATION: SAN ANDREAS, CA 95249					
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E6	0

GENERAL NOTES:

- INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
- WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
- OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
- AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.



FB7 Flange Brace Detail

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
 LICENSED PROFESSIONAL ENGINEER
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA


SPLICE PLATE & BOLT TABLE									
Mark	Qty Top	Qty Bot	Int	Type	Dia	Length	Width	Thick	Length
SP-1	4	4	0	A325	3/4"	2"	6"	1/2"	2'-3 1/8"
SP-2	4	4	0	A325	3/4"	2"	6"	1/2"	1'-4 7/8"

BASE PLATE TABLE			
Col Mark	Width	Thick	Plate Size Length
BP-1	6"	3/8"	10 1/2"

STIFFENER TABLE				
Mark	Stiff Mark	Width	Plate Size Thick	Length
RF1-1	ST1	2 1/2	1/4"	20"

MEMBER TABLE								
Mark	Web Depth		Web Plate		Outside Flange		Inside Flange	
	Start/End	Thick	Length	Thick	Length	W x Thk x Length	W x Thk x Length	
RF1-1/RF1-3	10.0/20.0	0.134	164.1			5 x 1/4" x 184.4	5 x 1/4" x 164.4	
	20.0/20.0	0.156	23.6			5 x 1/4" x 28.9		
RF1-2/RF1-4	20.0/10.0	0.134	91.2			5 x 1/4" x 240.0	5 x 1/4" x 91.7	
	10.0/10.0	0.134	222.7			5 x 1/4" x 94.5	5 x 1/4" x 221.0	
	10.0/10.0	0.134	24.0				5 x 1/4" x 24.0	

▽ FLANGE BRACES: FBxx (1 or 2)
 xx=length(in)
 (1) One Side; (2) Two Sides
 A - L2X2X1/4
 C - L2X2X1/8



RIGID FRAME ELEVATION: FRAME LINE 2 3 4 5

GENERAL NOTES:

- BOLTED JOINTS WITH A325 TYPE 1 BOLTS GREATER THAN 1/2" DIAMETER ARE SPECIFIED AS PRE-TENSIONED JOINTS IN ACCORDANCE WITH THE MOST RECENT EDITION OF THE RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS. PRE-TENSIONING CAN BE ACCOMPLISHED BY USING THE TURN-OF-NUT METHOD OF TIGHTENING, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT-TENSION-INDICATOR AS ACCEPTABLE TO THE INSPECTING AGENCY AND BUILDING OFFICIAL. INSTALLATION INSPECTION REQUIREMENTS FOR PRE-TENSIONED JOINTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.2) USING TURN-OF-NUT/CALIBRATED WRENCH/TWIST OFF TYPE TENSION CONTROL BOLTS/DIRECT TENSION INDICATOR] METHOD IS SUGGESTED. THE CONNECTIONS ON THIS PROJECT ARE NOT SLIP CRITICAL.
- ALL FIELD CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 BOLTS.
- INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER: CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E7	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt




SPLICE PLATE & BOLT TABLE										STIFFENER TABLE					
Mark	Qty	Top	Bot	Int	Type	Dia	Length	Width	Thick	Length	Mark	Stiff Mark	Width	Plate Size Thick	Length
SP-1	4	4	0		A325	3/4"	2"	6"	1/2"	2'-3 1/8"	RF2-1	ST1	2 1/2	1/4"	18"
SP-2	4	4	0		A325	3/4"	2"	6"	1/2"	1'-4 7/8"					

BASE PLATE TABLE			
Col Mark	Width	Thick	Plate Size Length
BP-1	6"	3/8"	10 1/2"

MEMBER TABLE								
Mark	Web Depth		Web Plate		Outside Flange			Inside Flange
	Start/End	Thick	Length	Thick	W x Thk x Length	W x Thk x Length	W x Thk x Length	
RF2-1	10.0/12.9	0.134	60.0		6 x 1/4" x 184.4	6 x 1/4" x 60.1		
	12.9/18.0	0.156	127.4		5 x 1/4" x 26.8	6 x 3/8" x 103.9		
RF2-2	20.0/10.0	0.134	93.2		5 x 1/4" x 240.0	5 x 1/4" x 93.7		
	10.0/10.0	0.134	222.7		5 x 1/4" x 96.5	5 x 1/4" x 221.0		
	10.0/10.0	0.134	24.0			5 x 1/4" x 24.0		

▽ FLANGE BRACES: FBxx (1 or 2)
 xx=length(in)
 (1) One Side; (2) Two Sides
 C - L2X2X1/8
 A - L2X2X1/4G



RIGID FRAME ELEVATION: FRAME LINE 6 7 8

GENERAL NOTES:

- BOLTED JOINTS WITH A325 TYPE 1 BOLTS GREATER THAN 1/2" DIAMETER ARE SPECIFIED AS PRE-TENSIONED JOINTS IN ACCORDANCE WITH THE MOST RECENT EDITION OF THE RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS. PRE-TENSIONING CAN BE ACCOMPLISHED BY USING THE TURN-OF-NUT METHOD OF TIGHTENING, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT-TENSION-INDICATOR AS ACCEPTABLE TO THE INSPECTING AGENCY AND BUILDING OFFICIAL. INSTALLATION INSPECTION REQUIREMENTS FOR PRE-TENSIONED JOINTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.2) USING TURN-OF-NUT/CALIBRATED WRENCH/TWIST OFF TYPE TENSION CONTROL BOLTS/DIRECT TENSION INDICATOR] METHOD IS SUGGESTED. THE CONNECTIONS ON THIS PROJECT ARE NOT SLIP CRITICAL.
- ALL FIELD CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 BOLTS.
- INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER: CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E8	0


May 19, 2021
Stephanie Lynn Schwindt
 Drawing has been digitally signed
STEPHANIE LYNN SCHWINDT
 LICENSED PROFESSIONAL ENGINEER
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA



PARTITION WALL FRAMING @ GRID 4

MEMBER TABLE		
PARTITION 1		
MARK	PART	LENGTH
PC-1	8F25C16	17'-8"
G-10	8X25Z16	17'-6 3/4"
G-11	8X25Z16	17'-2 3/4"
G-12	8X25Z16	19'-4"

CONNECTION PLATES	
FRAME LINE 4	
ID	MARK/PART
1	PC22-2
2	PC22-3



PARTITION 1 RIGHT SHEETING & TRIM
PANELS: 26 Gauge PBR - Polar White

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP






Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	E9	0




May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt





PURLIN ANTI-ROLL CLIP

Framed Opening - Jamb Brace at Eave Strut to Purlin



A5	Purlin To Bearing Frame Single Cold Form Rafter	Date Nov '19
Page MB-A5		Rev 01

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER: CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET1	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt


 LICENSED PROFESSIONAL ENGINEER
 Stephanie Lynn Schwindt
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA



B4	Cold Form Endwall Column To Rafter	Date Aug '20
Page MB-B4		Rev 01



B16	Corner Column To Bearing Frame Single Cold Form Rafter	Date Jun '17
Page MB-B16		Rev 00



C4	Girt To Cold Form Column	Date Jun '17
Page MB-C4		Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER: CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET2	0

May 19, 2021
Stephanie Lynn Schwindt
 Drawing has been digitally signed.


 LICENSED PROFESSIONAL ENGINEER
 STATE OF CALIFORNIA



D4	Girt To Cold Form Corner Column	Date Oct '19
Page MB-D4		Rev 01



D17	Girt To Cold Form Rotated Corner Column	Date Jun '17
Page MB-D17		Rev 00




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER	OWNER:	CALAVERAS COUNTY WATER DISTRICT				
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET3	0


May 19, 2021
 Drawing has been digitally signed.
Stephanie Lynn Schwindt



* - Refer To Anchor Rod Setting Plan For Dimension



Bolted Clips - Framed Opening Connections - Cold Form and Hot Rolled Base, Girt, Header, and Sill to Jamb



E8

Cold Form Endwall Column Base Plate

Date Dec '18
 Rev 01

F10

Endwall Bearing Frame - Cold Form Rafter Splice At Ridge

Date Jun '17
 Rev 00

Page MB-E8

Page MB-F10

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET4	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt

Bolted Clips - Framed Opening Connections - Cold Form and Hot Rolled Cee - Three and Four Sided Openings


Page AC01320
Date May '19 Rev 03

Note: All Horizontal Members within clear Opening are Clipped and attached to Jamb with 1/2" Fin Head Bolts.




Three Sided Framed Opening


** Girt within opening is provided when Framed Opening is to be paneled over.



Four Sided Framed Opening



* - Refer To Anchor Rod Setting Plan For Dimension



E8	Cold Form Endwall Column Base Plate	Date Dec '18	B19X	Endwall Column To Rigid Frame Rafter	Date
Page MB-E8		Rev 01	Page		Rev



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET5	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA



* - Refer To Anchor Rod Setting Plan For Dimension

Framed Opening - Jamb Brace at Eave Strut to Purlin



L1	Single Cold Form Jamb/Sub Jamb To Low Side Eave Strut	Date Dec '17	E8	Cold Form Endwall Column Base Plate	Date Dec '18
Page MB-L1		Rev 00	Page MB-E8		Rev 01

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP





Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET6	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt

* Similar Connection at Rafter
 ** Flat Washer WF500 Has A Larger Outside Diameter Than Flat Washer WFH500 And Is To Be Located Next To The Slope Washer



Q3	Rod Brace Attachment At Web	Date Mar '18
Page MB-Q3		Rev 01

Screw Application

Page TH06006
 Date May '19 Rev 01

Standard Grade


Description	Fastener Number	Application
1/4"-14 x 7/8" Type 2	4A	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	17A	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	17B	Member Screw (Up To 6" Insulation)

Long Life

Description	Fastener Number	Application
1/4"-14 x 7/8" Type 1	4	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	3	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	3A	Member Screw (Up To 6" Insulation)

PBR Panel - Southern Standard and Southern Large Edgecraft Rake Trim
 Purlin Extension - PBR Soffit

Page TPR17002
 Date Jul '20 Rev 00



Note: For some special conditions the outside rib of the finish panel may fall short of the rake trim. Use the rake extension trim for this condition. Field cut the rake trim and rake extension trim if required.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER: CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET7	0



May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt

 Stephanie Lynn Schwindt
 C 90667
 Civil Engineer
 STATE OF CALIFORNIA



R2	Anchor Rods At Frame Column	Date Dec '17
Page MB-R2		Rev 00

* - Refer To Anchor Rod Setting Plan




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP

Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com


PROJECT: CALAVERAS COUNTY WATER DISTRICT
 CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
 LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET8	0

May 19, 2021
 Drawing has been digitally signed
Stephanie Lynn Schwindt





All Roof Members Except As Noted Below



At Eave Strut, Panel End Lap And Peak Purlin

Note:
Screw patterns shown satisfy U.L. 90
requirements for roof.



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com




PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER
LOCATION: SAN ANDREAS, CA 95249
OWNER: CALAVERAS COUNTY WATER DISTRICT

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET9	0



May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA



Wall panel must be held off of base trim a minimum of 1/4" to prevent bottom of wall panel from rusting.



(See CP05005)



Note:
Install optional ridge insulation trim F684 as insulation and roof sheeting is being applied. Temporary attachment, if required, is not by metal building manufacturer.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER
OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET10	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
C 90667
Civil Engineer
STATE OF CALIFORNIA


PBR Wall Panel
Outside Corner - On Module

Page
PW03001
Date
Apr '19
Rev
08




PBR Soffit at Sheeted Wall

Page
GD14000
Date
May '19
Rev
06



PBR Roof - Edgcraft Eave Gutter End Lap Installation

Page
TPR04002
Date
Jul '20
Rev
00



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP






Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER
OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET11	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
C 90667
Civil Engineer
STATE OF CALIFORNIA



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET12	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
STATE OF CALIFORNIA
C 90667
Civil Engineer

PBR Roof Panel
Peak Box At Fixed Ridge

Page
GPR05001
Date Jul '20 Rev 07




Trim Profile	Roof Panel Location	Peak Box			
		Southern Standard	Southern Large	Northern Standard	Northern Large
Cascading		F1519	F1585	F1672	F1760
Classic		F160	F4153	F381	F1024
Contoured		F2219	F2285	F2372	F2460
Signature		F916	F3853	F236	F1018
Edgecraft	SL <= 3/4"	F6028	F6029	F6030	F6031
Edgecraft	>3/4" <= 3"	F6036	F6037	F6038	F6039

Note:
Flashing profile varies dependent on the building order. Attachment as illustrated is applicable for all profiles.

PBR Roof - Edgecraft Eave Gutter Expansion Installation - 100'-0" Maximum



Page
TPR04003
Date Jul '20 Rev 00



	Gutter		Gutter End Cap	Expansion Cap	Expansion Cover
Southern Standard	F6120	F6000RL	F6012 (9) Fastener #14	F6008	F6004 (7) Fastener #14
Southern Large	F6121	F6001RL	F6013 (13) Fastener #14	F6009	F6005 (11) Fastener #14
Northern Standard	F6122	F6002RL	F6014 (11) Fastener #14	F6010	F6006 (7) Fastener #14
Northern Large	F6123	F6003RL	F6015 (18) Fastener #14	F6011	F6007 (13) Fastener #14

PBR Roof Panel
Edgecraft Rake Trim End Lap Installation Detail - 3/4" thru 1 3/4" Wall Panel

Page
TPR05010
Date Sep '20 Rev 01



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP






Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET13	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt

Light Transmitting Panel (LTP)
PBR Roof Panel
Standard Placement Guidelines

*Note: Roof Panel and Light Transmitting Panel to span a minimum of (2) purlin spaces.
A minimum of 4" is required for panel endlaps. The non-insulated LTP may be field cut or endlap under the up-hill roof panel a maximum of 1'-0". Insulated LTP should not be cut in field.



U2	Bolts At Rigid Frame Ridge Rafter Connection	Date Jun '17	U3	Bolts At Rigid Frame Rafter To Column Connection	Date Jun '17
Page MB-U2		Rev 00	Page MB-U3		Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT							
CUSTOMER:	THE STEEL BUILDER			OWNER:	CALAVERAS COUNTY WATER DISTRICT			
LOCATION:	SAN ANDREAS, CA 95249							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE	
	5/11/21	N.T.S.	1	A	18-B-20989	DET14	0	

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA

Flush Canopy - At Eave - Welded Clip
End Frame - setback 4" or Greater


Page PF05032-X
Date Feb '11 Rev. 00



NOTES: ALL BOLTS TO BE 1/2" UNLESS NOTED.
FOR REQUIRED LENGTH REFER TO GRIP
TABLE ON CUSTOM ERECTION DRAWINGS.
CANOPY RAFTER CONNECTIONS AND STIFFENERS
DEPICTED WILL VARY PER DESIGN REQUIREMENTS.

Slimline Canopy At Eave - Welded Clip
Column Depth 1'-3" or Greater - By-Pass Girts


Page PF05130X
Date May '19 Rev. 02



Note:
1) Low Side Canopy shown, High Side Canopy similar with Canopy Purlins facing uphill.
2) All Bolts to be 1/2" unless noted. For required length refer to the Grip Table on Erection Drawings.
3) Canopy Rafter connections and stiffeners depicted will vary per Design requirements.

PBR Roof
Canopy at Low Eave - PBR Soffit

Page GD14042
Date Nov '15 Rev. 01



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET15	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA


Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.


Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls

Note: Panel position is shown with Panel Rib and Opening on 1'-0 module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com




PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET16	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
C 90667
Civil Engineer
STATE OF CALIFORNIA

PBR Wall Panel - Three Sided Framed Opening - Field Notch and Bend Tabs at Head Trim


Page PW07025
Date Mar '20 Rev 05

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




PBR Wall Panel - Three Sided Framed Opening Jamb Trim Field Cut Details

Page PW07027
Date Mar '20 Rev 04



PBR Wall Panel - Three Sided Framed Opening "Optional" Channel Closure Trim

Page PW07028
Date May '19 Rev 04



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER	OWNER:	CALAVERAS COUNTY WATER DISTRICT				
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET17	0



May 19, 2021

Stephanie Lynn Schwindt

Drawing has been digitally signed

PBR Wall Panel - Three Sided Framed Opening - Jamb Trim Installation

Page PW07029
Date Mar '20 Rev 05




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Opening on 1'-0" module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

PBR Wall Panel - Three Sided Framed Opening Head Trim Installation

Page PW07030
Date Oct '19 Rev 03



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER:	CALAVERAS COUNTY WATER DISTRICT		
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET18	0


May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA

DBCI Roll Up Door - Series 1900 Thru 2250 - Non Drive Side
 Small Mounting Plate / Mounting Bracket
 Header Attaches to Jamb Extending Above Framed Opening Height

Page AC00822
 Date May '17 Rev 00



Small Mounting Plate/Bracket Elevation




Section A

Small Mounting Plate
 (Non Drive Side)


- Notes:
1. Drawing is to be Used in Conjunction With DBCI Installation Manual.
 2. Mounting Plate, Mounting Bracket and Attachment Bolts, Nuts and Washers are Provided by DBCI.
 3. Non Drive Side can be on the Left or Right Jamb.
 4. Drawings Shows the Non Drive Side of the Door on the Left Jamb Viewed From the Inside.

DBCI Roll Up Door - Series 1900 Thru 5250 - Drive Side
 Large Mounting Plate / Mounting Bracket
 Header Attaches to Jamb Extending Above Framed Opening Height

Page AC00822
 Date May '17 Rev 00



Large Mounting Plate/Bracket Elevation



Section A

Large Mounting Plate
 (Drive Side)

- Notes:
1. Drawing is to be Used In Conjunction With DBCI Installation Manual.
 2. Mounting Plate, Mounting Bracket and Attachment Bolts, Nuts and Washer Provided by DBCI.
 3. Drive Side can be on the Left or Right Jamb.
 4. Drawing Shows the Drive Side of the Door on the Right Jamb Viewed From the Inside.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
 Mount Pleasant, IA. (319) 385-8001
 Rocky Mount, NC. (252) 977-2131
 www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET19	0

May 19, 2021
 Drawing has been digitally signed
 Stephanie Lynn Schwindt




Notes:

- Continuous Vents comes with a 10'-0" long chain pull factory attached for single vent damper operation and is field removed when vents are required to be linked together for continuous damper operation.
- Pull bars have a turnbuckle factory attached at one end and a bolt/nut assembly at the other end and are used to link the vents together for continuous damper operation.
- Refer to GPR13209 for Optional Vent Operators.




Continuous Vent Parts



Continuous Vent Isometric View

Vent Preparation Before Installation:
The vent end caps are pre-formed for a 1:12 roof slope and require field modification to the end caps for roof slopes greater than 1:12 prior to installation. Field modification of the vent end cap is not required for roof slopes 1:12 and less.

Turn the ventilator over and place the vent on it's top. There are five punch marks representing different roof slopes. Draw a line between the corners and to appropriate roof slope punch mark. Field cut and remove that portion of the end cap. See drawings below.





End Skirt Installation:


Position end skirt onto the vent end cap. Be sure the down-turned angle of the end skirt is positioned on the inside and tight against the vent end cap.

Attach the end skirt to the vent end cap with (6) Fastener #14. See drawing below.


Note: If vents are to be linked together for continuous damper operation only one end skirt installation is required.




End Skirt Detail for Single Vent




End Skirt Detail for Multiple Vents End to End



Section at Ridge 9" Throat Vent



Section at Ridge 12" Throat Vent



Vent End Cap at Roof Slopes Less Than 1:12

Continuous Ridge Ventilator 9" or 12" Throat x 10'-0" Flat Base
PBR Roof Panel $\frac{1}{2}$:12 Thru 2 $\frac{1}{2}$:12 Roof Slope
With F52 Die Formed Ridgecap

Page GPR13200
Date Feb '16 Rev '00

NOTE:
The Metal Building Manufacturer does not recommend the use of Ridge Ventilators on PBR roof systems on gable buildings over 200'-0" in width (100'-0" max. roof plane) or with roof slopes less than 1:12 or greater than 6:12.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP





Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER
LOCATION: SAN ANDREAS, CA 95249
OWNER: CALAVERAS COUNTY WATER DISTRICT

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET20	0



May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
STATE OF CALIFORNIA
C 90667
Civil Engineer

NOTE:
If additional purlins occur between purlins shown in the isometric view add 9 Fastener #43L for each additional purlin









GENERAL NOTES:
1. The light transmitting panels are not designed or intended to bear the weight of any person walking, stepping, standing, or resting on them. THE MANUFACTURER DISCLAIMS ANY WARRANTY OR REPRESENTATION, EXPRESSED OR IMPLIED, that any person can safely walk, step, stand, or rest on or near the light transmitting panels, or that they comply with any OSHA regulation. It is the Users responsibility to ensure that the installation and use of the light transmitting panels comply with State, Federal and OSHA regulations and laws, including, but not limited to, guarding all light transmitting panels with screens, fixed standard railings, or other acceptable safety controls that prevent fall-through.
2. Non-insulated light transmitting panels may need to be cut in the field, if required, follow these steps: Up to five (5) LTP's may be cut at one time. A circular saw with a 24 tooth per inch blade, will work best. Cut slow and allow the blade to work without excess pressure. Allow the blade to cool between cuts.
3. It is suggested to pre-drill the light transmitting panels before installing fasteners. This will help prevent fractures which may cause possible leaks.
4. Remove drill shavings and metal filings from the surface of the panels at the end of each work day. Rust caused by these items can destroy the panel finish and void warranties.

INSTALLATION NOTES:
1. Install roof panel and insulation according to standard procedures up to the desired location of the LTP shown on the "ROOF SHEETING PLAN". Install the LTP Flashing F75 at both sides of the LTP opening. Apply double face tape (not provided by Metal Bldg. Mfr.) to the sides of the LTP Flashing F75 to secure the insulation see Sections A and B.
2. Install insulation above and below the LTP opening. Apply double face tape to the purlins to secure the insulation see Sections C and D.
3. Apply Tape Sealer HW507 at the panel sidelap as shown in Section A and the isometric view.
4. Apply Tape Sealer HW504 on top of the lower roof panel endlap (panel 2) and extend Tape Sealer HW507 6" over the top of the roof panel sidelap Tape Sealer HW507. See Section C and the isometric view.
5. Apply Tape Sealer HW507 on top of the LTP sidelap and Tape Sealer HW504 at upper endlap. Extend Tape Sealer HW507 6" over the top of the lower roof panel sidelap Tape Sealer HW504 and the upper roof panel endlap (panel 4). See section D and the isometric view.
6. Attach LTP panel at sidelaps with sidelap fastener at 10" o.c. and endlaps and purlins as shown in "Endlap and Purlin Fastener Layout".



PBR Light Transmitting Panel Assembly Parts
UL 90 Rated Roof Construction Number 542



Caution:
The following are examples of conditions that may cause condensation on Light Transmitting Panels:
(A) Projects where outside winter temperatures below 40° F are anticipated and where average winter interior relative humidity of 45% or greater is expected.
(B) Building usages with high humidity interiors, such as indoor swimming pools, textile manufacturing operations, food, paper or other wet process industrial plants.
(C) Construction elements that may release moisture after the roof is installed, such as interior concrete and masonry, plaster finishes, and fuel burning heaters. The Building Manufacturer is not responsible for determining if condensation will be an issue on any particular application.

Non-Insulated PBR Light Transmitting Panel (LTP) Non UL 90 Application or UL 90 Application		Page GPR25100
		Date Feb '20
		Rev 02

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP


PROJECT: CALAVERAS COUNTY WATER DISTRICT		OWNER: CALAVERAS COUNTY WATER DISTRICT					
CUSTOMER: THE STEEL BUILDER		LOCATION: SAN ANDREAS, CA 95249					
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET21	0



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
C 90667
Civil Engineer
STATE OF CALIFORNIA

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
Note: Panel position is shown with Panel Rib and Door on 1'-0 module. Location of Rib may vary depending on the Door Width and location. Field measure before cutting Panel and Trim.

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP




Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET22	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA


Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.


Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Door on 1'-0 module. Location of Rib may vary depending on the Door Width and location. Field measure before cutting Panel and Trim.

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP





Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET23	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Jamb Trim F482 and Alternate Jamb Trim F484
Front View
Right Jamb Trim as shown
Left Jamb Trim opposite hand



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER
OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET24	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA

PBR Wall Panel - Knock Down Door Jamb Trim Installation

Page PW09031
Date Mar '20 Rev 07




Note:
All Trim Is To Be Installed BEFORE Blanket Insulation Is Applied To Walls.
Location Of Panel Rib May Vary Depending On Door Width, Door Location And Panel Starting Location. Refer To Erection Drawings For Panel Layout. Field Measure Before Cutting Panel And Trim.

Alternate Jamb Trim F484

Press Broke Downspout Layout 4" x 5"


Page DP00020
Date Apr '19 Rev 02



Note:
1. Refer to the building erection drawings for the spacing of the downspouts.
2. Locate all downspouts over a panel major rib if possible.
3. Downspout straps F797 are Located at the bottom of a downspout, below a splice, and at a mid point of downspout longer than 10'-6". See DP00011 thru DP00014 for downspout strap fasteners
4. Field notch downspouts for lap as shown and cut to length.

Press Broke Downspout at Eave Canopy - 4" x 5" Downspout

Page DP00021
Date May '19 Rev 01



Alternate Detail

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP






Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET25	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
LICENSED PROFESSIONAL ENGINEER
Stephanie Lynn Schwindt
C 90667
Civil Engineer
STATE OF CALIFORNIA




(2) Door Jamb Extensions Are Required For All Knock Down Doors.

Extend Door Jamb Extension To The 7'-6" Girt Elevation And Attach To The Web Of The Girt With (4) Fastener #12A, Attach Door Jamb Extension Channel To Door Jamb With (6) Fastener #12A.

For Girt Elevations Above 7'-6" Refer To AC05132 For Door Jamb Extension Requirements.



Note:
If Girt Has A 3/4" Flange, Field Notch Jamb Extension Channel To Clear Girt Lip. Do Not Notch Girt Lip.



The Adequacy Of The 3/8" Base Anchor Is Not The Responsibility Of The Building Manufacturer. The Adequacy Of These Base Anchors Should Be Determined By A Qualified Foundation Engineer.

Verify Door Jamb Base Clip Dimensions With Patterns Shown Prior To Placement Of Door Anchors And Adjust Patterns If Needed.

Note: 12 1/4" Frames May Not Have Kerf Door Frame Feature Depending On Door Manufacturer.



Knock Down Door Anchor Placement


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER						
OWNER:	CALAVERAS COUNTY WATER DISTRICT						
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET26	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt



Horizontal Slide Window

Single Hung Window




Fixed Window
(FW2056, FW2060, FW3040, FW4040)

Fixed Window
(FW1070, FW2070)

- PBR Jamb Fin E91
(2) per Window
- Snap-On Trim E86
(2) per Window
- *Vinyl Insulation Retainer V03

*Vinyl Insulation Retainer V03 is optional and is not provided unless specified on the order documents



Jamb Stiffener/Window Isometric

Installation Notes:

Window jamb fins are designed for installation at major panel ribs only. Typically windows are located between the 7'-6" girt and the baseline of the applicable wall.

Windows are typically packaged with two PBR Jamb Fins E91 that are not installed on the window unit. Prior to window installation install the jamb fins into the extruded grooves on each side of the window by sliding the fin in from the bottom of the window. The jamb fin should end flush with the top of the window head fin.

As the wall panels are installed, locate the jamb stiffeners at the wall panel major ribs at the desired window locations. Attach the jamb stiffeners to the girt and base members with Fastener #12A, see Jamb Stiffener/Window Isometric. Locate and mark window opening from the outside of the building, see Panel Cutout table for cutout width and height. Make sure the panel cutout height is correct and the panels are cut square. Push the window up until the window head contacts the upper wall panels. Make sure the window is square and level. Attach window unit with jamb fins installed to the jamb stiffeners with Fastener #12A at each corner. Apply Urethane Tube Sealant HW540 to both jamb fins, see Jamb Stiffener/Window Isometric.

Apply Urethane Tube Sealant HW540 to both sides of the inside panel closure and insert the closures between the wall panel and insulation at the window head and sill, See Section B.

Attach window head and sill to wall panels with #17A Fasteners at a 5", 7", 5" O.C., see Fastener Spacing at Window Head and Sill. Note: Fasteners are installed from the inside of the building at the window sill. Attach wall panels to window jamb fins/jamb stiffeners with Fastener #17A at 1'-0" O.C., see Section A.

Apply Urethane Tube Sealant HW540 along both sides between the window jambs and the wall panel to close any gaps. From the outside apply a continuous bead around the outside of the panel profile at the panel base, see Section B.

Install Snap-On Trim E86 at each jamb.


Vinyl Insulation Retainer Notes:
The optional Vinyl Insulation Retainer V03 can be installed before or after the window is installed. Install the retainer into the groove on the four interior sides, see Sections A and B. Notch back the tongue of the retainer at least 1/2" on both ends of either the horizontal or vertical retainers, this will allow the retainers to overlap at the four corners.

Panel Cutout			Panel Cutout		
Horizontal Slide			Fixed		
Window ID	Cutout Width	Cutout Height	Window ID	Cutout Width	Cutout Height
HS2016	1'-10"	1'-6 1/2"	FW1070	0'-10"	7'-0 1/2" (*)
HS3020	2'-10"	2'-0 1/2"	FW2056	1'-10"	5'-6 1/2"
HS3030	2'-10"	3'-0 1/2"	FW2060	1'-10"	6'-0 1/2"
HS3040	2'-10"	4'-0 1/2"	FW2070	1'-10"	7'-0 1/2" (*)
HS4030	3'-10"	3'-0 1/2"	FW3040	2'-10"	4'-0 1/2"
HS4040	3'-10"	4'-0 1/2"	FW4040	3'-10"	4'-0 1/2"
HS5030	4'-10"	3'-0 1/2"			
HS6020	5'-10"	2'-0 1/2"			
HS6030	5'-10"	3'-0 1/2"			
HS6040	5'-10"	4'-0 1/2"			


(*) Dimension is from baseline

Details shown are for horizontal slide windows. Single hung and fixed window installation details are similar.


Non Thermal Window (C225) Installation Details		Page
Horizontal Slide / Single Hung / Fixed Glass		AC08310
PBR Panel With Jamb Stiffeners		Date
		Rev
		Apr '19
		01




Section A - Jamb PBR Panel




Insulation Section at Window Head



Insulation Section at Window Sill




Section B - Head/Sill



Section C - Sill at Baseline

Fastener Spacing at Head and Window Sill

Note: Fastener location shown is for the window head, fasteners are installed from the inside at the window sill.



Insulation Section at Window Jamb




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com

PROJECT:	CALAVERAS COUNTY WATER DISTRICT						
CUSTOMER:	THE STEEL BUILDER			OWNER:	CALAVERAS COUNTY WATER DISTRICT		
LOCATION:	SAN ANDREAS, CA 95249						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET27	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt
STEPHANIE LYNN SCHWINDT
LICENSED PROFESSIONAL ENGINEER
STATE OF CALIFORNIA
C 90667
Civil Engineer



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET28	0

May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt


Transverse Partition - Roof Partition Trim Installation Section

Page
CP05003
Date
May '19
Rev
05



PBR Partition Panel
Base Angle With Flush Floor Base Without Trim

Page
PW02130
Date
Apr '19
Rev
00



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	5/11/21	FOR ERECTOR INSTALLATION	IES	IES	JOP



Columbus, MS. (662) 328-6722
Mount Pleasant, IA. (319) 385-8001
Rocky Mount, NC. (252) 977-2131
www.cecobuildings.com


PROJECT: CALAVERAS COUNTY WATER DISTRICT
CUSTOMER: THE STEEL BUILDER OWNER: CALAVERAS COUNTY WATER DISTRICT
LOCATION: SAN ANDREAS, CA 95249

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	5/11/21	N.T.S.	1	A	18-B-20989	DET29	0


May 19, 2021
Drawing has been digitally signed
Stephanie Lynn Schwindt

Building Anchorage

- To Determine That The Foundation Is Square, Measure Diagonal Dimensions To Be Sure They Are Of Equal Length.
- To Determine That The Foundation Is Level, Set Up A Transit Or Level And Use A Level Rod To Obtain The Elevation At All Columns.
- Carefully Check The Location Of All Anchor Rods Against The Anchor Rod Setting Plan Furnished By The Manufacturer. All Dimensions Must Be Identical To Assure A Proper Start-up.



It Is Extremely Important That Anchor Rods Are Placed Accurately And In Accordance With The Anchor Rod Setting Plan. All Anchor Rods Should Be Held In Place With A Template Or Similar Means, So That They Will Remain Plumb And In Correct Location During The Placement Of The Concrete. A Final Check Should Be Made After Completion Of The Concrete Work And Prior To The Steel Installation. This Will Allow Necessary Corrections To Be Made Before Costly Installation Labor And Equipment Arrives.




Pre-Erection Notes:

The Following Notes, Procedures And Suggested Recommendations Are Important Parts Of The Pre-Erection Process.

- Prior To The Time The Erection Crew Arrives, A Responsible Person Should Check The Job Site For Foundation Readiness, Square, And Accuracy And Anchor Rod Size And Location.

The Drawing Shown Below Indicates A Method Which May Be Used To Check The Foundation And Bolts For Square.




Measure Along Adjacent Sides Of Foundation Using A Pair Of Dimensions Shown. If The Diagonal Distance Between These Points Is As Noted, The Corner Is Square. Diagonal Measurements Between Opposite Anchor Rods Will Indicate If These Bolts Are Set Square.

AISC Code Of Standard Practice For Steel Building And Bridges Tolerances For Setting Anchor Rods

Anchor Rod Diameter, Inches (mm) *Horizontal Variation, Inches (mm)

$\frac{3}{4}$ " and $\frac{7}{8}$ " (19 And 22 mm)	$\frac{1}{4}$ " (6 mm)
1", $1\frac{1}{4}$ ", $1\frac{1}{2}$ " (25, 31, 38 mm)	$\frac{3}{8}$ " (10 mm)
$1\frac{3}{4}$ ", 2", $2\frac{1}{2}$ " (44, 50, 63 mm)	$\frac{1}{2}$ " (13 mm)




Erection Tolerances


ERECTION BRACING:

It Is The Responsibility Of The Erector To Determine, Furnish And Install All Temporary Supports Such As Temporary Guys, Beams, Falsework, Cribbing, Or Other Elements Required For The Erection Operation (In Accordance With Section 7.10.3 Of ANSI/AISC 303, Code Of Standard Practice For Steel Building And Bridges).


COLUMN ALIGNMENT TOLERANCES



ALIGNMENT TOLERANCE FOR MEMBERS WITH FIELD SPLICES



MEZZANINE BEAM HEIGHT TOLERANCE



General Erection Notes


1.) All Structural Framing Members, Purlins, Girts, Clips, Flange Braces, Bolts, Bracing Systems, Roof And Wall Panels, Etc. Must Be Installed As Shown On Erection Drawings.

2.) It Is Extremely Important, Especially During Construction, That Panels At The Eaves, Rakes And Ridges Be Kept Secure.

Panel Cautions And Notes

To Minimize Potential Of Corrosive Action At The Bottom Edge Of Wall Panels, The Contractor Must Assure That The Following Procedures Are Followed:

- The Concrete Foundation Should Be Cured For A Minimum Of Seven (7) Days Before Wall Panels Are Installed. (Uncured Concrete Is Highly Alkaline And Metal Panels Can Undergo Varying Degrees Of Corrosive Attack When In Direct Contact With The Concrete.) After The First Week Of The Curing Cycle, The Reaction Between Metallic Coatings On Steel And The Concrete Is Essentially Halted.
- Top Of Finish Grade At Building To Be A Minimum Of Four (4) Inches Below Bottom Of Panel.
- Finish Grade Is To Slope Away From Building To Ensure Proper Drainage.
- Upon Completion Of Finish Grading, All Dirt Is To Be Cleaned From Around Base Of Wall Panel Where It May Have Collected In Panel Notch Or On Base Trim.



Fastener Installation

Correct Fastener Installation Is One Of The Most Critical Steps When Installing Roof/Wall Panels. Drive The Fastener In Until It Is Tight And The Washer Is Firmly Seated. Do Not Overdrive Fasteners. A Slight Extrusion Of Neoprene Around The Washer Is A Good Visual Tightness Check. Always Use The Proper Tool To Install Fasteners. A Fastener Driver (Screw Gun) With A RPM Of 1700-2000 Should Be Used For Self-Drilling Screws. A 500-600 RPM Fastener Driver Should Be Used For Self-Tapping Screws. Discard Worn Sockets, These Can Cause The Fastener To Wobble During Installation.

Note: Always Remove Metal Filings From Surface Of Panels At The End Of Each Work Period. Rusting Filings Can Destroy The Paint Finish And Void Any Warranty.



Tape And Tube Sealant

Proper Tape And Tube Sealant Application Is Critical To The Weather Tightness Of A Building. Tape Sealant Should Not Be Stretched When Installed. Apply Only To Clean, Dry Surfaces. Keep Only Enough Sealants On The Roof That Can Be Installed In A Day. During Warm Weather, Store Sealants In A Cool Dry Place. During Cold Weather (below 60°) Sealants Must Be Kept Warm (60°-90°) Until Application. After Tape Sealant Has Been Applied, Keep Protective Paper In Place Until Panel Is Ready To Be Installed.

Important Note


All Details, Recommendations And Suggestions Contained In This Erection Guide Of This Drawings Set Are For General Guidelines Only, And Not Meant To Be All-inclusive. Industry Accepted Installation Practices With Regard To All Areas Not Specifically Discussed In This Section Should Be Followed. Only Experienced, Knowledgeable Installers Familiar With Accepted Practices Should Be Used To Assure A Quality Project.

It Is Emphasized That The Manufacturer Is Only A Manufacturer Of Metal Building Components And Is Not Engaged In The Installation Of Its Products. Opinions Expressed By The Manufacturer About Installation Practices Noted In The Erection Guide Are Intended To Represent Only A Guide. Both The Quality And Safety Of Installation And The Ultimate Customer Satisfaction With The Completed Building Are Determined By The Experience, Expertise, And Skills Of The Installation Crews, As Well As The Equipment Available For Handling The Materials. Actual Installation Operations, Techniques And Site Conditions Are Beyond The Manufacturers Control.

May 19, 2021
Stephanie Lynn Schwindt
 Drawing has been digitally signed.
STEPHANIE LYNN SCHWINDT
 LICENSED PROFESSIONAL ENGINEER
 STATE OF CALIFORNIA
 C 90667
 Civil Engineer

PBR Roof Panels

For PBR Roofs With Ridge Panels, It Is Recommended That Both Sides Of The Ridge Be Sheeted Simultaneously. This Will Keep The Insulation Covered For The Maximum Amount Of Time And The Panel Ribs Can Be Kept In Proper Alignment For The Ridge Panel. This Is Critical On The PBR Panels So That The Ridge Caps Can Be Properly Installed. Check For Proper Coverage As The Sheeting Progresses.



Install The First Run Of Roof Panels Across The Building From Eave To Eave Or Eave To Ridge. To Allow Proper Installation Of The Rake Trim, The Starting Location For The First Panel Must Be As Shown In The Rake Details Included With The Erection Drawings. When The First Run Is Properly Located And Aligned With The Correct Endlaps And Eave Overhangs, Fasten To Purlins. Roof Panels Should Be Installed So That The Sidelap Is In A Direction Away From Prevailing Wind. Refer To Appropriate Lap Details Included With The Erection Drawings.

Install Remaining Roof Insulation And Panels. To Avoid Accumulative Error Due To Panel Coverage Gain Or Loss, Properly Align Each Panel Before It Is Fastened. Occasional Checks Should Be Made To Ensure That Correct Panel Coverage Is Maintained. Special Attention Should Be Given To Fastener, Sealant and Closure Requirements. Refer To Details Included With The Erection Drawings.

At Finishing End Of Roof, The Last panels May Require Field Modification For Installation Of Rake Trim. Refer To Rake Details Included With The Erection Drawings. DO NOT BACK LAP THROUGH FASTENED ROOF PANELS.

NOTE: Roof Types And Installation Requirements Will Vary. Refer To The Appropriate Details For Specific Panel Used.

IMPORTANT: Loose Fasteners, Blind Rivets, Drill shavings, Etc.. Must Be Removed From The Roof To Guard Against Corrosion.


Wall Panels

Proper Horizontal And Vertical Alignment Of Supporting Structure (Girts Or Other Framing) Is The Responsibility Of The Installer. Failure To Align The Secondary members Properly Prior To Wall Installation Can Have A Direct Impact On The Final Appearance And Performance Of The Installed Wall System For Which The Metal Building Manufacturer Is Not Responsible.


Before Installing Wall Panels, The Girts Must Be Aligned To A Level Position So That There Is No Visible Sag. This Should Be Done Directly Ahead Of Panel Installation.

Girt Leveling May Be Accomplished By Standing A Section Of Gable Angle Vertically Against The Outside Girt Flanges At Approximate Mid-bay Location. When Girts Are Level, Attach The Girt Flanges To The Angle With Vise Grip Pliers Or Temporary Screws. Wood Blocking Cut To Fit The Spaces May Also Be Used For Alignment.

Note: Temporary Girt Blocking Is Not Recommended On Concealed Fastener Panels. The Removal Of The Blocks After Panel Installation Can Cause Oil Canning.




Note: Wall Panel Type And Installation Details Will Vary. Refer To The Erection Drawings And Details For The Specific Panel Used For Your Building.




If Walls Are To Be Insulated With Blanket Insulation Over Girt Girt Flanges, Base And Eave, Place A Continuous Run Of Contact Tape Along The Eave Strut And Base Member.

Note: At The Base, Cut Off The Insulation A Minimum Of 1/2" Above The Bottom Of The Wall Panel. This Will Prevent The Insulation From Hanging Below The Wall Panel And Wicking Moisture.

Note: Additional Insulation May Be Required To Fill The Eave Strut And Prevent Condensation In Certain Climate Regions




Eave Detail
(See Erection Drawings)



Base Detail
(See Erection Drawings)


Sidewall Panels Should Be Installed So That The Panel Sidelap Is In A Direction Away From The Prevailing Wind. Refer To Appropriate Lap Detail Included With Erection Drawings.)

Note: Check Periodically To Ensure That All Panels Are Aligned And Plumb.




Note: After Drilling Panels, It Is Important To Clean Metal Filings Off All Panel Surfaces, Including Between Panels That Are Not Installed That Day, To Avoid Rust Stains.

Suggested Method Of Purlin Attachment For Building Accessories



* Denotes Material Not Provided By Metal Building Manufacturer.
The Total Hanger Load Shall Not Exceed The Design Collateral Load For The Building. Example:
5'-0" (Purlin Spacing) X 5'-0" (Hanger Spacing) X 6 PSF (collateral Load) = 150 Lbs.
See Cover Sheet For Design Collateral Load For This Building.
Note: If The Building Is Designed For 0 PSF Collateral Load, Then Adding Any Suspended System (i.e. Duct Work, Piping, Lights, Ceilings, Etc.) Will Correspondingly Reduce The Design Live Load.

Roof Curbs When Not Supplied By Building Manufacturer




The Curb Details Shown Illustrate The Building Manufacturers Recommended Curb Style And Installation Method. It Is The Erector/Installer's Responsibility To Provide The Proper Curb Style And Install Them In Accordance With The Procedures Established By These Details. Failure By The Erector/Installer To Follow These Recommendations May Result In The Curbs Damaging The Roof System Or Excluded From Warranties.

- All Roof Curbs To Be:
1. .080 Aluminum Or 18 Ga. Stainless Steel (No Galvalume® Or Galvanized).
 2. Panel Rib To Panel Rib (No Flat Skirt Or Lay-Over Curbs).
 3. Installed With Down Hill End Over Panel And Up Hill End Under Panel Application For Water Flow At Panel Splice.
 4. Up Lift Prevention For Clip Applied Roof Systems Are Required If:
 - a. Wind Loads Exceed 110 MPH.
 - b. Curb Base Crosses A Purlin.
 5. Supported on (4) Sides By Primary Or Secondary Framing.
 6. Maximum Single Curb Weight Recommended Is 1500 Lbs.


Roof Jack Installation when Not Supplied By Building Manufacturer

General Installation Notes

- ? Do Not Use Galvanized Roof Jacks, Lead Hats, Or Other Residential Grade Roof Jacks. These Roof Jacks Do Not Have 20 Year Service Life And In Case Of Lead Hats Will Cause Galvanic Corrosion Of The Roof Panel.
- ? Use EPDM Rubber Roof Jacks With An Integral Aluminum Band Bonded Into The Perimeter Of The Base. EPDM Roof Jacks Have A Temperature Range From -65°F To 212°F. Use Silicone Roof Jacks For High Temperatures. Silicone Roof Jacks Have A Temperature Range Of -100°F To 437°F.
- ? Retrofit Roof Jacks Are Available For Applications In Which The Top Of The Pipe Is Inaccessible, Eliminating The Possibility Of Sliding The Roof Jack Over The Top Of The Pipe.
- ? Do Not Use Tube Sealant To Seal The Roof Jack To The Roof Panels. Use Roll Tape Sealer Between The Roof Jack And The Roof Panel And Attach The Roof Jack To The Roof Panel With Fastener #4 1/4" x 3/8" LL SD W/Washer At 1" O.C. Around The Base Of The Roof Jack. See Table Below For Quantities.
- ? Trim The Top Of The Roof Jack To Fit Over The Pipe, Roll Down The Roof Jack Over The Pipe And Apply Tape Sealer For The Perimeter Of The Roof Jack Base Between The Roof Jack And The Roof Panel. Apply Tape Sealer Around The Pipe And Install A Stainless Steel Clamp (Not By Bldg. Mfr.) Over The Top Of The Roof Jack And Firmly Tighten To Form A Secure Compression Seal.
- ? If The Pipe Diameter Is So Large To Block The Flow Of Water Down The Roof Panel, A Flat Base Roof Curb Must Be Installed Into The Roof And The Roof Jack Will Be Sealed To The Curb. A Two Piece Curb May Be Required When The Top Of The Pipe Is Inaccessible.
- ? In Northern Climates, The Pipe Penetration Should Be Protected From Moving Ice Or Snow With A Snow Retention System Immediately Up Slope From The Pipe.



Install Pipe In Center To Allow Base Of Roof Jack To Lay Flat on Panel. Cannot Encompass More Than 75% Of Panel.



May 19, 2021

Stephanie Lynn Schwindt

